

TES INC.

TECHNICAL CASE STUDY

SPARTA TILT & LOAD

UNDERGROUND LOADING,
LIFTING AND TRANSPORT

Custom engineered for underground
material-handling requirements.

WE KEEP YOUR MINE MOVING.



Illustrative underground setting




OPERATIONAL BACKGROUND

ORIGINAL MINE REQUIREMENT

The mine approached TES about a boom truck, with a need to move waste bins underground. The discussion shifted to a custom build that would remove the need for coordinating two machines.

OBJECTIVE | Retain crane capability and add a loading and transport method.



Illustrative bin-handling scene

REPORTED EQUIPMENT DEPENDENCY BOOM TRUCK + SECOND VEHICLE —————> BIN MOVEMENT



DESIGN REQUIREMENTS

MATERIAL-HANDLING REQUIREMENTS

Retain boom-truck functions while adding a loading method for suitable bin and equipment movements.




MINE REQUIREMENT	EQUIPMENT RESPONSE
Load without another machine for each movement	Tilt deck and integrated winch
Transport the loaded bin	Rear transport deck
Retain lifting and positioning	HIAB crane
Navigate travelways and set up for handling	Articulated carrier; separate travel and working envelopes



EQUIPMENT ENGINEERING

EQUIPMENT CONFIGURATION & INTEGRATION

Tilt deck, winch and crane
on the SPARTA carrier.



1 HIAB CRANE

Separate lifting and
positioning function.

2 WINCH SYSTEM

Draws suitable loads
onto the rear deck.

3 TILT DECK

Inclined loading surface
and transport deck.

HYDRAULIC SYSTEM

Pumps and hydraulic system
identified in the TES assembly.

DECK INTERLOCKS

Separate safety and lift
interlock systems are listed.



OPERATING CONFIGURATIONS

TILT-DECK LOADING & TRANSPORT



INCLINED DECK AND WINCH / ILLUSTRATIVE UNDERGROUND SETTING



LEVEL-DECK LOAD ARRANGEMENT

The winch draws suitable loads onto the inclined deck. The deck returns to level for secured transport.

DRAWING REFERENCE	VALUE
Deck length	3.811 m
Level deck height	1.092 m

Payload, winch and restraint limits are specific to the delivered configuration.

Upper right: original surface photograph




TECHNICAL REFERENCE

HIAB CRANE


CAPACITY

S-CLX 100 D-2

Crane lifting capacity is separate from the deck transport rating.



TES CRANE-DEPLOYED REFERENCE VIEW



ORIGINAL HIAB LOAD DIAGRAM

WORKING RADIUS	RATED CAPACITY
1.9 m	3,900 kg
3.0 m	2,550 kg
4.2 m	1,820 kg
5.5 m	1,400 kg

5.7 m MAXIMUM HYDRAULIC OUTREACH

Use the installed load chart and approved stabilization conditions.




VEHICLE GEOMETRY

UNDERGROUND ACCESS & WORKING ENVELOPE

Travelway clearance and handling space are separate checks.

REFERENCE CONFIGURATION 811351000	VALUE
Tramming height	2.554 m
Overall width	2.588 m
Overall length	8.723 m
Outer turning radius	9.144 m
Inner turning radius	6.096 m
Steering articulation	±38°

Load height, tilted-deck movement and crane setup
require separate clearance assessment.



ORIGINAL TES TURNING-ENVELOPE DRAWING



REPORTED MINE APPLICATIONS

DEPLOYMENT & ADDITIONAL USE

MULTIPLE APPLICATIONS REPORTED

The mine purchased multiple units and extended their use beyond the original waste-bin requirement.

ORIGINAL APPLICATION

Movement of waste bins underground.

ADDITIONAL REPORTED USE

Transport of disabled forklifts and other equipment.



Surface photograph illustrates the load arrangement; it is not a customer recovery record.



PROJECT ASSESSMENT

OPERATIONAL ASSESSMENT

EQUIPMENT ALLOCATION

Suitable movements can be assigned to one integrated loading and transport vehicle.

FLEET APPLICABILITY

Fleet requirements still depend on concurrent tasks, load limits, access and machine availability.


Multiple-unit purchasing and broader use are reported.
Handling-time and cost savings have not been quantified.

WE KEEP YOUR MINE MOVING.

DIMENSIONS & SPECIFICATIONS

Key dimensions, capacities and major system specifications for the SPARTA UTD20000 Tilt & Load.


SIDE ELEVATION (TRAVEL)




FRONT ELEVATION



CRANE ENVELOPE (DEPLOYED)



DECK PLAN (TOP VIEW)



CRANE

Model	HIAB S-CLX 100 D-2
Hydraulic outreach	5.7 m (18 ft 8 in)
Stabilization	boom stabilizer
Lifting capacity at 1.9 m	3,900 kg (8,600 lb)
Lifting capacity at 3.0 m	2,550 kg (5,620 lb)
Lifting capacity at 4.2 m	1,820 kg (4,010 lb)
Lifting capacity at 5.5 m	1,400 kg (3,090 lb)

POWERTRAIN & CHASSIS

Engine	Volvo TAD582VE (Stage V / Tier 5 equivalent)
Transmission	DANA 32000 Series
Axles	Spring Applied Hydraulic Release (SAHR)
Braking	integrated SAHR wet disc brakes (6 disc)
Tires	12.00-20 pneumatic
Frame	heavy-duty construction frame
Driveline	four-wheel drive articulated steer carrier

DECK & TRANSPORT

Deck dimensions	2.44 m (96 in) x 3.81 m (150 in)
Deck capacity, level	9,070 kg (20,000 lb)
Tilt angle	33°
Deck capacity, tilted	9,070 kg (20,000 lb)
Empty weight	13,600 kg (30,000 lb) estimate, confirm on scale

MOBILITY


Tramming height	2.553 m (100.5 in)
Inside turning radius	6.096 m (240 in)
Outside turning radius	9.144 m (360 in)

ELECTRICAL & SAFETY

24V electrical system
Audio back-up alarm
Engine oil pressure switch
LED lighting installed
Lock out on master switch
White strobe light included

CONTACT US

MineReach - Compact Design. Expanded Capability



705-855-4254



sales@tesinc.ca



**3695 Ford Drive,
Chelmsford, Ontario, Canada**



SPARTA MineReach

